Roof condensation: assess the build-up

A reflective roof or a metal fixing does not by itself diagnose the problem.

Build Supply | SulfRock | Intelligent Panel Systems | HomePod

1 Find the moisture source

Check indoor humidity, air leakage, rain ingress and construction moisture before selecting a remedy.

2 Assess the whole roof

Review covering, insulation, deck, underlay, air/vapour control and any designed ventilation.

3 Check cold bridges

Fixings and junctions can create colder areas. Consider their effect within the thermal and condensation design.

4 Detail control layers

Make air-control layers continuous and place vapour-control measures according to the assessed construction.

5 Treat spray foam carefully

It is not a universal condensation cure. Existing roof condition and moisture risk require assessment before installation.

6 Verify the design

Use appropriate condensation or hygrothermal assessment, product evidence and inspection before concealing work.

Repair leaks and establish the moisture strategy before adding insulation.

REFERENCE GUIDANCE

BSR: spray foam moisture research
GOV.UK: resistance to moisture research

Use current product instructions and the approved project design. For regulations, confirm the UK nation, applicable edition and transitional arrangements.

Help us keep our information accurate.

If you notice an error, outdated information or something that needs clarification in this document, please let us know.
Report an Issue: Visit our website and select Report a Website or Document Issue.
buildsupplyltd.co.uk